

SECTION 611

ACCEPTANCE PROCEDURES

DISTRICT 3 TSP –MODIFIED FOR TALLAHASSEE/LEON COUNTY

IV. ACCEPTANCE, INSPECTION AND TRANSFER

Article 611-2 of the Standard Specifications is expanded as follows:

At the time of conditional acceptance of the project, the traffic signal(s) shall be inspected by the Traffic Operations Section of the Florida Department of Transportation located in Chipley, Florida and a representative of the maintaining agency. At that time, the Contractor shall furnish all necessary test equipment including a bucket truck, for the testing and inspection of traffic signals and loops.

The Contractor shall complete the "Signalization Checklist", latest revision, prior to the time of the conditional acceptance inspection. This checklist is found in Appendix A of District Three's Standard Guidelines for Traffic Signal Design and Installation. This checklist along with the loop and grounding measurements will be sent to Mr. Gene Syfrett of Traffic Operations in Chipley and a copy shall be sent to the maintaining agency before the conditional acceptance signal inspection is scheduled.

Final Acceptance of Traffic Signal Installation(s) and Transfer of Maintenance Form 700-010-22 must be completed by the signal contractor, a representative of the maintaining agency, and the FDOT inspector at the end of the project. The form is available through the District Three Traffic Operations Office and in Appendix E of The Standard Guidelines for Traffic Signal Design and Installation. A copy of this completed form shall be sent to the maintaining agency.

At the time of conditional acceptance of the project, the Contractor shall furnish the inspector three complete sets of as-built plans, with one set of these intended for delivery by the FDOT inspector to the maintaining agency.